

**CITY OF MOOSE JAW
ENGINEERING DEPARTMENT**



**2017 SEWER LINING
COLLECTION/RESIDENTIAL
CONTRACT NUMBER 17-002**

NOTICE TO BIDDERS



The City of Moose Jaw is accepting tenders for the work described below. Please submit the documents listed and described in the Instructions to Bidders in a sealed opaque envelope, clearly identified with Bidder's name, Project name, and Owner's name on the outside.

City of Moose Jaw
Engineering Department, 3rd Floor
228 Main Street North
Moose Jaw, SK, S6H 3J8

Tender Close:
Friday, April 28, 2017
2:00 PM CST

INTENT

The City of Moose Jaw operates around 170 kilometers of residential underground sewage collection infrastructure of varying ages. The composition of this infrastructure varies based on the year of installation, but is largely comprised of Vitrified Clay Tile (VCT), Asbestos Cement and Poly Vinyl Chloride (PVC). On occasion concrete, cast iron and steel pipes have been used. The VCT and PVC sewer lines have longer service lives than the cast iron and steel mains. The structural condition has been the main selection criteria but also infiltration and proximity to work within the same contract.

SCOPE OF WORK

Cleaning and installation of CIPP on clay tile: 1307 Lin. Metres. The successful contractor will be required to clean and install a Cured-in-Place (CIPP) resin-impregnated liner that is continuous and bonded to the host pipe, 883m of 200mm and 424m of 250mm around the City.

Videos of the pipe can be downloaded from the City web site or can be picked up from the Engineering Department of the City of Moose Jaw, upon request.

LOCATION

The sanitary sewer main to be restored of their sanitary Main sewer sections of the sewage collection system in different locations of the City. The pipe sections are continuous. Locations map is attached with the tender document.

DATE OF CONSTRUCTION

Start Date: As soon as possible

Completion Date: December 31, 2017