

**CITY OF MOOSE JAW
ENGINEERING DEPARTMENT**



**2017 TRUNK SEWER REPLACEMENT
CONTRACT NUMBER 17-004**

NOTICE TO BIDDERS



The City of Moose Jaw is accepting tenders for the work described below. Please submit the documents listed and described in the Instructions to Bidders in a sealed opaque envelope, clearly identified with Bidder's name, Project name, and Owner's name on the outside.

City of Moose Jaw
Engineering Department, 3rd Floor
228 Main Street North
Moose Jaw, SK, S6H 3J8

Tender Close:
Thursday, May 25, 2017
2:00 PM CST

INTENT

A portion of the trunk sanitary sewer line diameter changed that reduced the trunk sewer system. The sanitary line was built in 1911 and the diameter was reduced sometime after that. That manhole is close to the Thunder Creek. The engineering department has decided to abandon the old sanitary trunk line and construct a new PVC 600mm Sanitary line from MH14943 to MH14944 and abandon old sewer and the MH that is close to the Thunder Creek (MH13230, Appendix A).

SCOPE OF WORK

Supply and installation of 600 mm sanitary trunk sewer line 111 Lin. Metres, and replacement of one manhole 3.7 m deep. The successful bidder will be required to install PVC CSA Certified B182.2-M90 sewer pipe to the given specifications.

LOCATION

The sanitary sewer trunk to be replaced is on the north side of zero Block of Maple St. W. by Thunder Creek. There is a gravel pathway along the replacement route. Access can be gained from Main Street South. Potential bidders are requested to visit the location prior to bid.

Thunder Creek runs through this area and seepage could occur during excavation. The contractor will need to control water in the excavation. They may need to bypass when connecting the new sewer to the old.

DATE OF CONSTRUCTION

Start Date: As soon as possible
Completion Date: July 31, 2017